ERRATUM / ADDENDUM NOTICE:

DEPARTMENT /	PTB NUMBER	BID NUMBER / PROJECT DESCTIPTION	CONTACT PERSON
INSTITUTION			
DEPARTMENT OF	PTB NO. 19	SCMU 10-24/25-0009: PANEL FOR THE	SCM RELATED ENQUIRIES - Email is the
TRANSPORT		SURFACING OF VARIOUS ROADS	preferred first contact option.
	DATED : 08 TH	CONSTRUCTED BY EASTERN CAPE	
	AUGUST 2024	DEPARTMENT OF TRANSPORT (EC DOT'S) IN	Mr. P. Nqikashe – Cell No.: 067 419
		HOUSE UNITS FOR A PERIOD OF 36	8001 – Email.:
		MONTHS.	philasande.nqikashe@ectransport.gov.za
			Ms. A. Mketsu – Cell No.: 067 411 2177
		REASON FOR THE ERRATUM	– Email.:
			abongile.mketsu@ectransport.gov.za
		1. The Bill of Quantities has been amended	
		and replaces and the original BoQ.	
		·	TECHNICAL ENQURIES - Email is the
		2. Briefing clarification meeting - non	preferred first contact option.
		compulsory	
			Mr. M. Goxa - Cell No.: 064 880 1945 -
		Bidders are to kindly download the amended Bill	Email Address:
		of Quantities from the departmental website on	mvuyisi.goxa@ectransport.gov.za
		www.ectransport.gov.za (Procurement/bid	Mr. P. Ngqola – Cell No, 066 381 7987 –
		notices) and from e-Tender Portal publication	Email.:
		website. www.etenderportal.gov.za.	phakamisa.ngqola@ectransport.gov.za
			F. G.
		CLOSING DATE IS EXTENDED FROM	
		FRIDAY 06 TH SEPTEMBER 2024 TO	
		MONDAY 23 RD SEPTEMBER 2024 AT	
		11:00	

Payment		Description	11.14	B.II. 10 .II	5.	Estimated	
Item	LIC Items	Description	Unit	Billed Quantity	Rate	Amount	
1500		SECTION 1500: ACCOMMODATION OF TRAFFIC					
B15.01		Accommodating traffic and maintaining temporary deviations	Month	36		-	
45.00		Earthworks for temporary deviations					
15.02		a) Shaping of temporary deviations	km	26	-	-	
		b) Cut and borrow to fill	m³	1		Rate Only	
		c) Cut to spoil	m³	1	-	Rate Only	
B15.03		Temporary traffic control facilities					
	LI	a) Flagmen	Man-day	6336	-	-	
		b) Portable STOP and GO-RY signs	No	4	-		
		d) Amber flicker lights	No	1	-	Rate Only	
		e) Road signs, R- and TR- series, (900 mm series)	No	20	-		
		f) Road signs, TW-series	No	20	-	-	
		g) Road signs, STW-, DTG-, TGS- and TG-series	2				
		(excluding delineators and barricades)	m²	40	-	-	
		h) Delineators (DTG 50J) (800 x 200 mm):					
		1) Single	No	200		-	
		2) Mounted back to back	No	200		-	
		i) Moveable barricade/road sign combination (8 m wide road closed type)	No	4	-	-	
		j) Traffic cones (750 mm high)	No	10	-		
		k) Single guardrails attached to posts	m	1	-	-	
		I) Movable barriers (guardrail sections attached to welded posts and footplates)	m	1	-	-	
		m) Two-way communication devices	No	8	-	-	
		n) Other traffic control measures ordered by the Engineer.				-	
		(i) Provision of other traffic control measures	Prov Sum	1	-	-	
		(ii) Handling costs and profit in respect of B15.03(n)(i)	%	100 000,00	%		
B15.04		Relocation of traffic control facilities	L/Sum	1	-	-	
15.05		Gravelling and repair of temporary deviations and existing gravel shoulders used as temporary deviations				-	
		a) Temporary deviations	km	5	-		
		b) Existing gravel shoulders	km	5	-	-	
15.06		Watering of temporary deviations	km	10	-	-	
45.07		Blading by road grader of:				-	
15.07		a) Temporary deviations	km	10	-		
		b) Existing roads used as temporary deviations	km	5	-	-	
15.08		Repairs, alterations and/or additions to existing roads used as temporary deviations	Prov Sum	1.00	-	-	
15.10		Accommodation of traffic where the road is constructed in half widths	km	7	-	-	
B15.11		Traffic Signals for road closures, including at bridges.	Prov Sum	1	-	-	
B15.16		Traffic safety officer - Full-time	man-month	36	-	-	
B15.17		Penalties for non-conpliance with traffic management plans					
		a) Fixed penalty per occurrence	No	1		- 5 000,00	
		b) Time related penalty	hr	1		- 500,00	
1500		SECTION 1500: ACCOMMODATION OF TRAFFIC		TO SUMMARY PA	.GE	R	

Payment	LICItama	Description	l loi4	Billed	uest for Quotes (R	
Item	LIC Items	Description	Unit	Quantity	Rate	Estimated Amount
1800		SECTION 1800 : DAYWORKS				
D.10.01		Labour		_		
B18.01		a) Unskilled labourer	Hr	9	-	-
		b) Semi-skilled labour	Hr	9	-	-
		c) Skilled labour	Hr	9	-	-
		d) Survey Ganger	Hr	9	-	-
		e) Artisan or mechanic	Hr	9	-	-
		f) Roads Foreman	Hr	9	-	-
B18.02		Personnel engaged outside normal working hours 1) Outside normal working hours and Saturdays	Hr	9	-	-
		a) Unskilled labourer				
		b) Semi-skilled labour	Hr	9	-	-
		c) Skilled labour	Hr	9	-	-
		d) Survey Ganger	Hr	9	-	-
		e) Artisan or mechanic	Hr	9	-	-
		f) Roads Foreman	Hr	9	-	-
		2) Sundays and Public Holidays	Hr	9	_	
		a) Unskilled labourer	111	9	•	•
		b) Semi-skilled labour	Hr	9	-	-
		c) Skilled labour	Hr	9	-	-
		d) Survey Ganger	Hr	9	-	-
		e) Artisan or mechanic	Hr	9	-	-
		f) Roads Foreman	Hr	9	-	-
B18.03		Construction Plant				
		a) Pneumatic tyred roller	Day	9	-	-
		b) Compressor unit with capacity to generate 3 m3/min at 650 kpa	Day	9	-	-
		c) Mobile crane	Day	9	-	-
		d) Self prppelled Mechanical broom	Day	9	-	-
		e) Self proppelled Chipspreader	Day	9	-	-
		f) 3000L Bitumen Hand sprayer trailer	Day	9	-	-
		g) 6 000L Bitumen distributor truck	Day	9	-	-
		h) 11 000 litres bitumen distributor truck	Day	9	-	-
B18.04		Materials and Equipment				-
		a) Procurement of material and equipment	Prov Sum	1	1 500 000,00	1 500 000,00
		b) Handling costs and profit in respect of B18.04(a).	%	1 500 000,00	%	
B18.05		Transport				
		a) Bus or similar for transporting labour	Day	9	-	-
1800		DAYWORKS	CARRIED F	ORWARD TO SU	MMARY PAGE	R

N.B: The billed quantities are for evaluation purposes only. The actual quantities will be quantified with Request for Quotes (RFQs).

Payment	I IC Homo	Description	l lm:4	Billed	Rate	Estimated
Item	LIC Items	Description	Unit	Quantity	Nate	Amount
2400		SECTION 2400: ASPHALT AND CONCRETE BERMS				
24.01		Asphalt berms, 80/100 pen grade continuous graded asphalt				
	Ц	a) Placed where there are no guardrails	m	1	-	Rate Only
	Ц	b) Placed at existing guardrails (newly installed)	m	1	-	Rate Only
24.02		Concrete berms				
	Ц	a) Placed where there are no guardrails	m	1	-	Rate Only
	Ц	b) Placed at existing guardrails (newly installed)	m	1	-	Rate Only
24.03		Prime and tack coats				
		a)(i) Prime coat under asphalt berm MC-30 cut back bitumen	m²	1	-	Rate Only
		a)(ii) Prime coat under concrete berm MC-30 cut back bitumen	m²	1	-	Rate Only
		b) Tack coat, 30% stable grade emulsion	m²	1	-	Rate Only
24.04		Transition sections for NJ type parapets (at bridge approaches)	No	1	-	Rate Only
2400	SECTION 2400: ASPHALT AND CONCRETE BERMS CARRIED FORWARD TO SUMMARY PAGE					

SECTION 4100

Payment	LIC Items Descripti	Description	Unit	Billed Quantity	Rate	Estimated
Item	LIC Itellis	Description	Description			Amount
4100		SECTION 4100: PRIME COAT				
B41.01		Prime coat:				
D41.01		f) Colprime E or similar (All areas)	litre	172172		-
41.02	LI	Aggregate for blinding	m²	20800		-
41.03	LI	Extra over Item 41.01 for applying the prime coat in areas accessible only to hand held equipment	litre	43043		-
4100		SECTION 4100: PRIME COAT	CARRIED FORWARD TO SUMMARY PAGE		R	

N.B: The billed quantities are for evaluation purposes only. The actual quantities will be quantified with Request for Quotes (RFQs).

Payment	11011	Do contest ou	l lade	Billed	Rate	Estimated
Item	LIC Items	Description	Unit	Quantity		Amount
4200		SECTION 4200: ASPHALT BASE AND SURFACING				
42.04		Tack coat of 30% stable-grade emulsion	I	1	-	Rate Only
42.05		Binder variations:				
		(a) A-E2 modified bitumen	t	1	-	Rate Only
42.06		Variations in Active Filler Content:				
		(a) Cement	t	1	-	Rate Only
		(b) Lime	t	1	-	Rate Only
42.08		100 mm cores in asphalt paving	No.	1	-	Rate Only
42.09		Asphalt surfacing on bridge decks				
		a) 50 mm Continuously graded				
		(i) medium grade asphalt surfacing using B12 road grade bitumen	t	1	-	Rate Only
		(ii) medium grade asphalt surfacing using A-E2 modified grade bitumen	t	1	-	Rate Only
4200	SECT	TION 4200: ASPHALT BASE AND SURFACING	CARRIED FORWARD TO SUMMARY PAGE			

SECTION 4600

Payment	LIC Items	Description	Unit	Billed	Rate	Estimated
Item	LIC items		Onit	Quantity		Amount
4000		SECTION 4600: BITUMINOUS SINGLE SEAL WITH				
4600		SLURRY (CAPE SEAL)				
B46.01		Bituminous single seal with 19 mm Grade 1 aggregate and slurry (2 coats of slurry) on roadway with:				
		a) 70/100 penetration grade bitumen in tack coat and 65% cationic spray grade emulsion in the penetration coat	m²	20800		-
		b) A tack coat comprising of:				
		(i) 70% polymer modified cationic spray-grade emulsion of Class SC-E1 (Winter)	m²	20800		-
		(ii) Hot applied polymer modified bitumen binder of Class S-E1 (Summer)	m²	20800		
		c) 65% Cationic spray grade emulsion in both tack coat and penetration spray for cape seal on sidewalks	m²	4000		
46.03		Bituminous binder variations:				
		f) Spray-grade emulsion (65% bitumen)	litre	1		Rate Only
		g) Spray-grade emulsion (70% bitumen)	litre	1		Rate Only
46.04		Aggregate variations:				
		b) 19 mm Nominal sized aggregate	m³	3952		
46.05		Variations in the rate of application of the slurry	m³	790		
46.06		Slurry application rate variations	t	1		Rate Only
46.07		Variation in active filler content (active filler to be ordinary cement)	t	1		Rate Only
46.08		Extra over items B46.01 for work in areas inaccessible to mechanical equipment	m²	1		Rate Only
4600	SECTION 4600: BITUMINOUS SINGLE SEAL WITH SLURRY CARRIED FOR		FORWARD TO PAGE	SUMMARY	R	

N.B: The billed quantities are for evaluation purposes only. The actual quantities will be quantified with Request for Quotes (RFQs).

Payment	LIC Items	Do continuio u	l lmit	Dillad Oversity	Rate	Estimated
Item	LIC Items	Description	Unit	Billed Quantity		Amount
7000		SECTION 7300: CONCRETE BLOCK PAVING FOR				
7300		ROADS				
73.01		Concrete block paving, using standard 230mm x 110mm pavers.				
	LI	(a) At rest areas and view sites, using 60 mm thick pavers	m²	1		Rate Only
	LI	(b) On sidewalks at the bridge approaches, using 60 mm thick pavers	m²	1		Rate Only
	Ш	(c) On driveways, pathways and parking areas, using 80 mm thick pavers.	m²	1		Rate Only
B73.02		Concrete edge and intermediate beams .				
	LI	(a) Cast in-situ at back of sidewalks	m³	1		Rate Only
	LI	(b) Pre-cast edge beams, Figure 12 kerbs,	m	1		Rate Only
73.03		Provision of approved herbicide and ant poison.				
		a) Provision of materials	Sum PC	1	500 000,00	500 000,00
		b) Contractor's charges and profit added to the prime cost sum	%	500 000,00	%	
7300		SECTION 7300: CONCRETE BLOCK PAVING FOR ROADS	CARRIED OVER TO SUMMARY PAGE			R

SECTION 8100

Payment	I IC Homo	LIC Items Description	Unit	Dillad Overtity	Data	Estimated
Item	LIC Rems	Description		Billed Quantity	Rate	Amount
8100		SECTION 8100: TESTING MATERIALS AND				
0100		WORKMANSHIP				
81.02		a) Other special tests requested by the engineer	Prov Sum	1	50 000,00	50 000,00
		b) Handling costs and profit in respect of 81.02(a).	%	50 000,00	%	
8100	SE	CTION 8100: TESTING MATERIALS AND WORKMANSHIP	CARRIED FORWARD TO SUMMARY PAGE			R

ENGINEER'S COST ESTIMATE SUMMARY OF SCHEDULE OF QUANTITIES

	SCHEDULE A	Estimate amount
1500	ACCOMMODATION OF TRAFFIC	R
1000	DAMANODVO	
1800	DAYWORKS	R
2400	ASPHALT AND CONCRETE BERMS	-
4100	PRIME COAT	R
1100		
4200	ASPHALT BASE AND SURFACING	
4600	BITUMINOUS SINGLE SEAL WITH SLURRY (CAPE SEAL)	R
7300	CONCRETE BLOCK PAVING FOR ROADS	R
8100	TESTING MATERIALS AND WORKMANSHIP	R
	SUBTOTAL 1	R
	Contingencies - 5.0%	R
	SUBTOTAL 2	R
PI	D TOTAL (CARRIED OVER TO THE FORM OF OFFER)	R R